

**DEPARTMENT OF TRANSPORTATION**  
DIVISION OF ENGINEERING SERVICES  
OFFICE ENGINEER, MS 43  
1727 30<sup>TH</sup> STREET  
P.O. BOX 168041  
SACRAMENTO, CA 95816-8041  
FAX (916) 227-6214  
TTY 711



*Flex your power!  
Be energy efficient!*

December 8, 2008

08-Riv,SBd-15-82.8/84.1,0.0/6.3  
08-472214  
ACIM-015-1(151)106E  
HFL-HIHL(001)E

Addendum No. 4

Dear Contractor:

This addendum is being issued to the contract for CONSTRUCTION ON STATE HIGHWAY IN SAN BERNARDINO AND RIVERSIDE COUNTIES IN AND NEAR ONTARIO, RANCHO CUCAMONGA, AND NORCO FROM ROUTE 15/60 SEPARATION TO SEVENTH STREET UNDERCROSSING.

Submit bids for this work with the understanding and full consideration of this addendum. The revisions declared in this addendum are an essential part of the contract.

Bids for this work will be opened on December 11, 2008.

This addendum is being issued to revise the Project Plans, the Notice to Bidders and Special Provisions, and the Bid book.

Project Plan Sheet 5 is revised as follows:

"The thickness dimension of RANDOM SLAB REPLACEMENT is revised from 299 mm PCC to 229 mm PCC."

Project Plan Sheet 12 is revised as follows:

"The pavement section RANDOM SLAB REPLACEMENT 213 mm (PRECAST SLAB) is revised to 203 mm PRECAST PCC SLAB over 10 mm LEVELING MATERIAL."

Project Plan Sheet 13 is revised as follows:

"The pavement section RANDOM SLAB REPLACEMENT  $\Omega$  213 mm (PRECAST SLAB) is revised by adding RANDOM SLAB REPLACEMENT 203 mm (PRECAST SLAB) over 10 mm LEVELING MATERIAL."

Project Plan Sheet 281 is revised as follows:

"The station callouts for END TEMPORARY RAILING (TYPE K) and END TEMPORARY DETAIL 27B on the south side of Ontario Mills Parkway are changed from STA 111+60 to STA 101+30."

08-Riv,SBd-15-82.8/84.1,0.0/6.3  
08-472214  
ACIM-015-1(151)106E  
HFL-HIHL(001)E

Project Plan Sheet 281 is revised as follows:

"The station callout for END TEMPORARY RAILING (TYPE K) on the north side of Ontario Mills Parkway is changed from STA 111+60 to STA 101+60."

Project Plan Sheet 410 is revised as follows:

"In the first TRAFFIC CONTROL DEVICES table, the quantities of TEMPORARY RAILING (TYPE K) and TEMPORARY TRAFFIC SCREEN for STAGE 1 are revised from 16548 to 14518, and their SUBTOTALS changed from 26990 to 24960."

Project Plan Sheet 411 is revised as follows:

"In the first TRAFFIC CONTROL DEVICES table, the TOTALS for TEMPORARY RAILING (TYPE K) and TEMPORARY TRAFFIC SCREEN are changed from 51571 to 49541."

In the Special Provisions, Section 5-1.04, "COMPENSATION ADJUSTMENTS FOR PRICE INDEX FLUCTUATIONS," the table of the first paragraph is revised by adding the following row:

"395501	LIQUID ASPHALT MC-70 (PRIME COAT)"
---------	------------------------------------

In the Special Provisions, Section 10-1.24, "MAINTAINING TRAFFIC," Charts Nos. 34, 35, 36, 37, 38, 39, 40, 41, 42 and 43 are added as attached.

In the Special Provisions, Section 10-1.48, "REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)," is revised as attached.

In the Bid book, in the "Bid Item List," Items 23 and 25 are revised as attached.

To Bid book holders:

Replace page 4 of the "Bid Item List" in the Bid book with the attached revised page 4 of the Bid Item List. The revised Bid Item List is to be used in the bid.

Inquiries or questions in regard to this addendum must be communicated as a bidder inquiry and must be made as noted in the Notice to Bidders section of the Notice to Bidders and Special Provisions.

Indicate receipt of this addendum by filling in the number of this addendum in the space provided on the signature page of the Bid book.

Submit bids in the Bid book you now possess. Holders who have already mailed their book will be contacted to arrange for the return of their book.

Inform subcontractors and suppliers as necessary.

Addendum No. 4  
Page 3  
December 8, 2008

08-Riv,SBd-15-82.8/84.1,0.0/6.3  
08-472214  
ACIM-015-1(151)106E  
HFL-HIHL(001)E

This office is sending this addendum by confirmed facsimile to all book holders to ensure that each receives it. A copy of this addendum is available for the Contractors' use on the Web site:

**[http://www.dot.ca.gov/hq/esc/oe/weekly\\_ads/addendum\\_page.html](http://www.dot.ca.gov/hq/esc/oe/weekly_ads/addendum_page.html)**

If you are not a Bid book holder, but request a book to bid on this project, you must comply with the requirements of this letter before submitting your bid.

Sincerely,

ORIGINAL SIGNED BY

ROBERT E. TRAVIS, Chief  
Office of Plans, Specifications & Estimates  
Division of Engineering Services - Office Engineer

Attachments

Chart No. 34																									
Complete Connector Closure Hours/Connector Lane Requirements																									
County: Riv					Route/Direction: 15/SB										PM: 51.5										
Closure Limits: SB 15 off to EB 60																									
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	1	1																1	1	1	1
Fridays	1	1	1	1	1	1																		1	1
Saturdays	1	1	1	1	1	1	1																	1	1
Sundays	1	1	1	1	1	1	1																	1	1
Legend:																									
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel <input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																									
REMARKS:																									

Chart No. 35																										
Complete Connector Closure Hours/Connector Lane Requirements																										
County: Riv					Route/Direction: 15/SB										PM: 51.9											
Closure Limits: SB 15 off to WB 60																										
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays	1	1	1	1	1	1																	1	1	1	1
Fridays	1	1	1	1	1	1																			1	1
Saturdays	1	1	1	1	1	1	1																		1	1
Sundays	1	1	1	1	1	1	1																		1	1
Legend:																										
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel <input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																										
REMARKS:																										

Chart No. 36																									
Complete Connector Closure Hours/Connector Lane Requirements																									
County: Riv							Route/Direction: 15/NB							PM: 51.8											
Closure Limits: NB 15 on from EB 60																									
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	1																		1	1	1
Fridays	1	1	1	1	1																		1	1	1
Saturdays	1	1	1	1	1																		1	1	1
Sundays	1	1	1	1	1																		1	1	1
Legend:																									
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel <input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																									
REMARKS:																									

Chart No. 37																									
Complete Connector Closure Hours/Connector Lane Requirements																									
County: Riv							Route/Direction: 15/NB							PM: 51.6											
Closure Limits: NB 15 on from WB 60																									
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	1																		1	1	1
Fridays	1	1	1	1	1																		1	1	1
Saturdays	1	1	1	1	1																		1	1	1
Sundays	1	1	1	1	1																		1	1	1
Legend:																									
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel <input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																									
REMARKS:																									

Chart No. 38																										
Complete Connector Closure Hours/Connector Lane Requirements																										
County: Sbd							Route/Direction: 15/NB							PM: 2.4												
Closure Limits: NB 15 off to WB 10																										
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays	1	1	1	1	1																			1	1	1
Fridays	1	1	1	1	1																			1	1	1
Saturdays	1	1	1	1	1																			1	1	1
Sundays	1	1	1	1	1																			1	1	1
Legend:																										
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel																										
<input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																										
REMARKS:																										

Chart No. 39																										
Complete Connector Closure Hours/Connector Lane Requirements																										
County: Sbd							Route/Direction: 15/NB							PM: 1.9												
Closure Limits: NB 15 off to EB 10																										
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays	1	1	1	1	1																			1	1	1
Fridays	1	1	1	1	1																			1	1	1
Saturdays	1	1	1	1	1																			1	1	1
Sundays	1	1	1	1	1																			1	1	1
Legend:																										
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel																										
<input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																										
REMARKS:																										

Chart No. 40																									
Complete Connector Closure Hours/Connector Lane Requirements																									
County: Sbd							Route/Direction: 15/NB							PM: 2.7											
Closure Limits: NB 15 on from EB 10																									
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1	1	1																		1	1
Fridays	1	1	1	1	1	1																		1	1
Saturdays	1	1	1	1	1	1																		1	1
Sundays	1	1	1	1	1	1																		1	1
Legend:																									
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel <input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																									
REMARKS:																									

Chart No. 41																										
Complete Connector Closure Hours/Connector Lane Requirements																										
County: Sbd							Route/Direction: 15/SB							PM: 2.0												
Closure Limits: SB 15 on from WB 10																										
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays	1	1	1	1																				1	1	1
Fridays	1	1	1	1																					1	1
Saturdays	1	1	1	1	1	1																		1	1	
Sundays	1	1	1	1	1	1																		1	1	
Legend:																										
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel <input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																										
REMARKS:																										

Chart No. 42																									
Complete Connector Closure Hours/Connector Lane Requirements																									
County: Sbd							Route/Direction: 15/SB							PM: 2.5											
Closure Limits: SB 15 off to WB 10																									
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Mondays through Thursdays	1	1	1	1																		1	1	1	1
Fridays	1	1	1	1																				1	1
Saturdays	1	1	1	1	1	1																		1	1
Sundays	1	1	1	1	1	1																		1	1
Legend:																									
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel																									
<input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																									
REMARKS:																									

Chart No. 43																										
Complete Connector Closure Hours/Connector Lane Requirements																										
County: Sbd							Route/Direction: 15/SB							PM: 2.7												
Closure Limits: SB 15 off to EB 10																										
FROM HOUR TO HOUR	24	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24	
Mondays through Thursdays	1	1	1	1																			1	1	1	1
Fridays	1	1	1	1																					1	1
Saturdays	1	1	1	1	1	1																			1	1
Sundays	1	1	1	1	1	1																			1	1
Legend:																										
<input type="checkbox"/> 1 Provide at least one connector lane open in direction of travel																										
<input type="checkbox"/> Work permitted within project right of way where shoulder or lane closure is not required.																										
REMARKS:																										

#### **10-1.48 REPLACE CONCRETE PAVEMENT (RAPID STRENGTH CONCRETE)**

Replace concrete pavement (Rapid Strength Concrete) shall consist of removing existing portland cement concrete pavement and underlying cement treated base and constructing rapid strength concrete (RSC) pavement as shown on the plans and in conformance with Section 40, "Portland Cement Concrete Pavement," of the Standard Specifications and these special provisions.

#### **DEFINITIONS**

The following definitions shall apply to this section:

1. EARLY AGE. – A time less than 10 times the final set time of the concrete.
2. FINAL SET TIME. – The elapsed time after initial contact of cement and water, or accelerator, if used, at which a specific penetration resistance of 27.6 MPa is achieved in conformance with the requirements in ASTM Designation: C 403.
3. OPENING AGE. – The age at which the concrete will achieve the specified strength for opening to public or Contractor traffic.

#### **PRE-OPERATION CONFERENCE**

The Contractor and subcontractors involved in construction operations of RSC shall meet with the Engineer at a pre-operation conference, at a mutually agreed time, to discuss methods of accomplishing all phases of the construction operation, contingency planning, and standards of workmanship for the completed item of work.

The Contractor shall provide the facility for the pre-operation conference. The Contractor's superintendent, foremen, subcontractors, field staff, plant personnel including plant supervisors, manager, quality control manager, and operator involved with RSC shall attend the pre-operation conference. The Contractor shall submit a list of participants to the Engineer for approval. The complete listing shall identify each participant's name, employer, title and role in construction of RSC. The pre-operation conference shall be held for no less than 2 hours. Construction operations of RSC shall not begin until the specified personnel have completed the mandatory pre-operation conference.

#### **JUST-IN-TIME TRAINING**

Just-In-Time Training (JITT) shall be mandatory, and consist of a formal joint training class on rapid strength concrete. Construction operations for rapid strength concrete shall not begin until the Contractor's and the Engineer's personnel have completed the mandatory JITT. The Contractor's personnel included in the list of participants for the Pre-Operation Conference along with the Engineer's representatives shall attend JITT.

The JITT session will be conducted for not less than 4 hours on rapid strength concrete. The training class may be an extension of the Pre-Operation Conference and shall be conducted at the project field location convenient for both the Contractor's and the Engineer's project staffs. Scheduling and completion of the JITT session shall be completed at least 5 working days prior to the start of construction of rapid strength concrete. The class shall be held during normal working hours.

The JITT instructor shall be experienced in the construction methods, materials, and test methods associated with rapid strength concrete. The instructor shall not be an employee of the Contractor or a member of the Engineer's field staff. A copy of the syllabus, handouts, and presentation material shall be submitted to the Engineer at least 7 days before the day of the training. Selection of the course instructor, the course content and training site shall be as mutually agreed to by the Contractor and the Engineer. The instructor shall issue a certificate of completion to the participants upon the completion of the class. The certificate shall include the course title, date and location of the class, the name of the participant, instructor's name, location and phone number.

The Contractor's or Engineer's personnel involved with rapid strength concrete operations will not be required to attend JITT if they have completed similar training within the previous 12 months of the date of the JITT for this project. The Contractor shall provide a certificate of class completion as described above for each staff member to be excluded from the JITT session. The final determination for exclusion of any staff member's participation will be as determined by the Engineer. All attendees of the JITT shall complete, and submit to the Engineer, an evaluation of the training. The course evaluation form will be provided by the Engineer.

It is expressly understood that Just-In-Time Training shall not relieve the Contractor of any responsibility under the contract for the successful completion of the work in conformity with the requirements of the plans and specifications.

## **REMOVING EXISTING PAVEMENT**

Exact limits of concrete pavement to be replaced will be determined by the Engineer.

Existing concrete pavement material shall be removed and replaced with RSC pavement within the same work period. In the event existing pavement or base materials are removed and the Contractor is unable to construct, finish, and cure RSC pavement prior to the specified traffic opening time, a temporary roadway structural section shall be constructed.

The outline of concrete pavement to be removed shall be sawed full depth with a power-driven saw except where the pavement is located adjacent to an asphalt concrete shoulder. Saw cuts within concrete pavement slabs shall be cut no more than 2 days prior to concrete pavement slab removal. Saw cuts made in work shifts prior to the actual removal work shift shall not be made parallel or diagonal to the traveled way and shall be cut so that traffic will not dislodge any pieces or segments.

Concrete pavement shall be removed by non-impacting methods. Each pavement panel shall be removed in one or more pieces without disturbance or damage to the underlying base.

Equipment used to remove concrete pavement within the sawed outline, shall not impact the surface of the concrete to be removed within 0.5-m of pavement to remain in place. Pavement removal shall be performed without damage to pavement or base to remain in place. Damage to pavement or base to remain in place, shall be repaired or removed and replaced. Repair, or removal and replacement of the damaged pavement and base shall be at the Contractor's expense and will not be measured nor paid for.

Removed materials shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

## **TEMPORARY ROADWAY STRUCTURAL SECTION**

Asphalt concrete and aggregate base, equal to the quantity of pavement removed during the work shift, shall be provided on site for construction of a temporary roadway structural section where existing pavement is to be replaced. The quantity and location of standby material shall be included in the Contractor's contingency plan in conformance with the requirements of these special provisions. Temporary roadway structural section shall be maintained and later removed as the first order of work when replace concrete pavement (Rapid Strength Concrete) operations resume. The temporary roadway structural section shall consist of 90-mm thick asphalt concrete over aggregate base. RSC not conforming to these special provisions for RSC may be used for temporary roadway structural section with the Engineer's approval.

Aggregate base for temporary roadway structural section shall be produced from commercial quality aggregates consisting of broken stone, crushed gravel, natural rough-surfaced gravel, reclaimed concrete and sand, or any combination thereof. Grading of aggregate base shall conform to the 19-mm maximum grading specified in Section 26-1.02A, "Class 2 Aggregate Base," of the Standard Specifications.

Asphalt concrete for temporary roadway structural section shall be produced from commercial quality aggregates and asphalt binder. Grading of aggregate shall conform to the 19-mm maximum, medium grading in Section 39-2.02, "Aggregate," of the Standard Specifications and asphalt binder shall conform to requirements for liquid asphalt SC-800 in Section 93, "Liquid Asphalts," of the Standard Specifications. Amount of asphalt binder to be mixed with the aggregate shall be approximately 0.3 percent less than the optimum bitumen content determined in conformance with the requirements in California Test 367.

Aggregate base and asphalt concrete for the temporary roadway structural section shall be spread and compacted by methods that will produce a well-compacted, uniform base, with a surface of uniform smoothness, texture and density. Surfaces shall be free from pockets of coarse or fine material. Aggregate base may be spread and compacted in one layer. Asphalt concrete may be spread and compacted in one layer. Finished surface of asphalt concrete shall not vary more than 15 mm from the lower edge of a 3.6-m  $\pm$ 0.06 m long straightedge placed parallel with the centerline and shall match the elevation of existing concrete pavement along the joints between the existing pavement and temporary surfacing.

Removed temporary roadway structural section materials shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, except that removed aggregate base may be stockpiled at the project site and reused for construction of temporary roadway structural sections. When no longer required, standby material or stockpiled material for construction of temporary roadway structural sections shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

## RAPID STRENGTH CONCRETE

### General

Rapid Strength Concrete (RSC) shall be a concrete made with hydraulic cement that develops opening age and 7-day specified modulus of rupture strengths.

Requirements of Sections 40-1.05, "Proportioning," and 90-1.01, "Description," of the Standard Specifications shall not apply.

Combined aggregate grading used in RSC shall be either the 37.5-mm, maximum grading, or 25-mm, maximum grading, at the option of the Contractor.

Cement for RSC shall be hydraulic cement as defined in ASTM Designation: C 219 and shall conform to the following requirements:

Test Description	Test Method	Requirement
Contraction in Air	California Test 527, W/C Ratio = $0.39 \pm 0.010$	0.053 %, max.
Mortar Expansion in Water	ASTM Designation: C 1038	0.04 %, max.
Soluble Chloride*	California Test 422	0.05 %, max.
Soluble Sulfates*	California Test 417	0.30 %, max.
Thermal Stability	California Test 553	60 %, min.
Compressive Strength @ 3 days	ASTM Designation: C 109	17 MPa

\*Test is to be done on a cube specimen, fabricated in conformance with the requirements in ASTM Designation: C 109, cured at least 14 days and then pulverized to 100% passing the 300- $\mu$ m sieve

At least 45 days prior to intended use, the Contractor shall furnish a sample of cement from each lot proposed for use and all admixtures proposed for use in the quantities ordered by the Engineer.

The Contractor shall submit uniformity reports for cement used in RSC to the Cement Laboratory at the Transportation Laboratory. Uniformity reports shall conform to the requirements in ASTM Designation: C 917, except that testing age and water content may be modified to suit the particular material. Uniformity reports shall be submitted at least every 30 days during RSC pavement operations.

Type C accelerating chemical admixtures conforming to the provisions in Section 90-4, "Admixtures," of the Standard Specifications may be used. In addition to the admixtures listed on the Department's current list of approved admixtures, citric acid or borax may be used if requested in writing by the cement manufacturer and a sample is submitted to the Engineer. Chemical admixtures, if used, shall be included in the testing for requirements listed in the table above.

At least 10 days prior to use in the trial slab, the Contractor shall submit a mix design for RSC that shall include the following:

1. Opening age
2. Proposed aggregate gradings
3. Mix proportions of hydraulic cement and aggregate
4. Types and amounts of chemical admixtures
5. Maximum time allowed between batching RSC and placing roadway pavement
6. Range of ambient temperatures over which the mix design is effective (10°C maximum range)
7. Final set time of the concrete
8. Any special instructions or conditions, including but not limited to, water temperature requirements when appropriate

The Contractor shall submit more than one mix design to plan for ambient temperature variations anticipated during placement of the roadway pavement. Each mix shall be designed for a maximum ambient temperature range of 10°C. The Contractor shall develop and furnish modulus of rupture development data for each proposed mix design. Modulus of rupture development data for up to 7 days shall be provided to the Engineer prior to beginning paving operations. Modulus of rupture development data may be developed from laboratory prepared samples. The testing ages for modulus of rupture development data shall include one hour before opening age, opening age, one hour after opening age, 24 hours, 7 days and 28 days.

Concrete pavement penetration requirements in Section 90-6.06, "Amount of Water and Penetration," of the Standard Specifications shall not apply to RSC.

RSC pavement shall develop a minimum modulus of rupture of as specified in "Pay Factor Adjustment for Low Modulus of Rupture" of these special provisions before opening to public or Contractor traffic. In addition, RSC pavement shall develop a minimum modulus of rupture of 4.2 MPa in 7 days after placement. RSC pavement that attains a modulus of rupture of less than specified may be accepted in conformance with "Pay Factor Adjustment for Low Modulus of Rupture" specified herein. Modulus of rupture shall be determined by averaging results from 3 beam specimens tested in conformance with the requirements in California Test 523. Beam specimens may be fabricated using an internal vibrator in conformance with the requirements in ASTM Designation: C 31. No single test shall represent more than the production of that day or 100 cubic meters, whichever is less.

Modulus of rupture at early age may be estimated using the correlation established during trial slab placement or by using results from beam specimens cured under atmospheric conditions and at a temperature within 3°C of the pavement. Modulus of rupture at other ages will be determined using beams cured and tested in conformance with California Test 523 except beams will be placed into sand between 5 and 10 times final set time or 24 hours, whichever is earlier. The Engineer will perform the testing to determine modulus of rupture values of the RSC pavement. The modulus of rupture, as determined above, will be the basis for accepting or rejecting the RSC pavement for modulus of rupture requirements.

**Pay Factor Adjustment for Low Modulus of Rupture**

Where planned replacement pavement nominal thickness is less than 255 mm, payment for replace concrete pavement (Rapid Strength Concrete) will be adjusted for low modulus of rupture tests as follows:

1. Replace concrete pavement (Rapid Strength Concrete) with modulus of rupture of 2.8 MPa or greater before the lane is opened to the traffic and 7-day modulus of rupture of 4.2 MPa or greater will be paid for at the contract price per cubic meter for replace concrete pavement (Rapid Strength Concrete).
2. Replace concrete pavement (Rapid Strength Concrete) with a 7-day modulus of rupture of less than 3.4 MPa will not be paid for, and shall be removed and replaced, at the Contractor's expense with replace concrete pavement (Rapid Strength Concrete) conforming to the requirements of these special provisions.
3. Replace concrete pavement (Rapid Strength Concrete) with modulus of rupture of 2.1 MPa or greater before the lane is opened to traffic and a 7-day modulus of rupture of equal to or greater than 3.4 MPa will be paid for at a percentage of the contract price per cubic meter for replace concrete pavement (Rapid Strength Concrete) in conformance with the percentages in the pay table below.
4. Replace concrete pavement (Rapid Strength Concrete) with modulus of rupture of less than 2.1 MPa when the lane is opened to traffic will be rejected and shall be removed and replaced at the Contractor's expense with replace concrete pavement (Rapid Strength Concrete) conforming to the requirements of these special provisions.

Percentage Pay Table

Modulus of Rupture (MPa) at opening to traffic	7-Day Modulus of Rupture (MPa)		
	Greater than or equal to 4.2	Less than 4.2 and greater than or equal to 3.8	Less than 3.8 and greater than or equal to 3.4
Greater than or equal to 2.8	100%	95%	90%
Less than 2.8 and greater than or equal to 2.4	95%	95%	90%
Less than 2.4 and greater than or equal to 2.1	80%*	80%*	80%*

\*Any replacement panels that develops one or more transverse cracks within 21 days after placement shall be removed and replaced at the Contractor's expense with replace concrete pavement (Rapid Strength Concrete) conforming to the requirements of these special provisions. A transverse crack is defined as a crack running from one longitudinal edge of the panel to the other.

Where planned replacement pavement nominal thickness is 255 mm or greater, payment for replace concrete pavement (Rapid Strength Concrete) will be adjusted for low modulus of rupture tests as follows:

1. Replace concrete pavement (Rapid Strength Concrete) with modulus of rupture of 2.3 MPa or greater before the lane is opened to the traffic and 7-day modulus of rupture of 4.2 MPa or greater will be paid for at the contract price per cubic meter for replace concrete pavement (Rapid Strength Concrete).
2. Replace concrete pavement (Rapid Strength Concrete) with a 7-day modulus of rupture of less than 3.4 MPa will not be paid for, and shall be removed and replaced, at the Contractor's expense with replace concrete pavement (Rapid Strength Concrete) conforming to the requirements of these special provisions.
3. Replace concrete pavement (Rapid Strength Concrete) with modulus of rupture of 1.8 MPa or greater before the lane is opened to traffic and a 7-day modulus of rupture of equal to or greater than 3.4 MPa will be paid for at a percentage of the contract price per cubic meter for replace concrete pavement (Rapid Strength Concrete) in conformance with the percentages in the pay table below.
4. Replace concrete pavement (Rapid Strength Concrete) with modulus of rupture of less than 1.8 MPa when the lane is opened to traffic will be rejected and shall be removed and replaced at the Contractor's expense with replace concrete pavement (Rapid Strength Concrete) conforming to the requirements of these special provisions.

Percentage Pay Table

Modulus of Rupture (MPa) at opening to traffic	7-Day Modulus of Rupture (MPa)		
	Greater than or equal to 4.2	Less than 4.2 and greater than or equal to 3.8	Less than 3.8 and greater than or equal to 3.4
Greater than or equal to 2.3	100%	95%	90%
Less than 2.3 and greater than or equal to 2.0	95%	95%	90%
Less than 2.0 and greater than or equal to 1.8	80%*	80%*	80%*

\*Any replacement panels that develops one or more transverse cracks within 21 days after placement shall be removed and replaced at the Contractor's expense with replace concrete pavement (Rapid Strength Concrete) conforming to the requirements of these special provisions. A transverse crack is defined as a crack running from one longitudinal edge of the panel to the other.

The Contractor shall pay to the State adjustments in payment for low modulus of rupture tests in conformance with the requirements specified in the tables in this section. The Department will deduct the amount of the adjustments from moneys due or that may become due, the Contractor under the contract.

**Proportioning**

Weighing, measuring and metering devices used for proportioning materials shall conform to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications and these special provisions.

Over and under dials, and other indicators for weighing and measuring systems used in proportioning materials shall be grouped so that the smallest increment for each indicator can be accurately read from the point at which the proportioning operation is controlled for ingredients batched at a central batch plant. In addition, indicators for weighing and measuring cement batched from a remote weighing system shall also be placed so that each indicator can be accurately read from the point at which the proportioning operation is controlled.

Aggregates shall be handled and stored in conformance with the provisions in Section 90-5.01, "Storage of Aggregates," of the Standard Specifications. Liquid admixtures shall be proportioned in conformance with the provisions in Section 90-4.10, "Proportioning and Dispensing Liquid Admixtures," of the Standard Specifications. Mineral admixtures shall be protected from exposure to moisture until used. Adequate facilities shall be provided to assure that mineral admixtures meeting the specified requirements are kept separate from other mineral admixtures to easily track the materials that are entering the work. Safe and suitable facilities for sampling mineral admixtures shall be provided at the weigh hopper or in the feed line immediately in advance of the hopper.

Weighing equipment shall be insulated against vibration or movement of other operating equipment. When the plant is in operation, the mass of each draft of material shall not vary from the designated mass by more than the tolerances specified herein. Each scale graduation shall be 0.001 of the usable scale capacity.

Aggregate shall be weighed cumulatively and equipment for the weighing of aggregate shall have a zero tolerance of  $\pm 0.5$  percent of the designated total batch mass of the aggregate. Equipment for the separate weighing of the cement shall have a zero tolerance of  $\pm 0.5$  percent of their designated individual batch drafts. Equipment for measuring water shall have a zero tolerance of  $\pm 0.5$  percent of its designated mass or volume.

The mass indicated for any individual batch of material shall not vary from the preselected scale setting by more than the following:

Material	Tolerance
Aggregate	$\pm 1.0$ percent of designated batch mass
Cement	$\pm 0.5$ percent of designated batch mass
Water	$\pm 1.5$ percent of designated batch mass or volume

Proportioning shall consist of dividing the aggregates into the specified sizes, each stored in a separate bin, and combining them with cement and water as provided in these special provisions. Dry ingredients shall be proportioned by mass. Liquid ingredients shall be proportioned by mass or volume.

At the time of batching, aggregates shall have been dried or drained sufficiently to result in stable moisture content, so that no visible separation of water from aggregate will take place during the proportioning process. In no event shall the free moisture content of the fine aggregate at the time of batching exceed 8 percent of its saturated, surface-dry mass.

If separate supplies of aggregate material of the same size group with different moisture content or specific gravity or surface characteristics affecting workability are available at the proportioning plant, withdrawals shall be made from one supply exclusively and the materials therein completely exhausted before starting upon another supply.

Cement shall be kept separate from the aggregates until released for discharge into the mixer. Cement shall be free of lumps and clods when discharged into the mixer. Fabric containers used for transportation or proportioning of cement shall be clean and free of residue before reuse.

Weigh systems for proportioning aggregate, and cement shall be individual and distinct from all other weigh systems. Each weigh system shall be equipped with a hopper, a lever system, and an indicator to constitute an individual and distinct material-weighing device.

For batches with a volume of one cubic meter or more, proportioning equipment shall conform to one of the following methods:

1. All ingredients shall be batched at a central batch plant and charged into a mixer truck for transportation to the pour site. Ingredient proportioning shall meet the requirements of Section 90-5, "Proportioning," of the Standard Specifications.
2. All ingredients except the cement shall be batched at a central batch plant and charged into a mixer truck for transportation to a remote located silo and weigh system for the proportioning of the cement. The remote system shall proportion cement for charging the mixer truck.
3. All ingredients except the cement shall be batched at a central batch plant and charged into a mixer truck for transportation to a remote location where pre-weighed, containerized cement shall be added to the mixer truck. The cement pre-weighing operation shall utilize a platform scale. The platform scale shall have a maximum capacity of 2.5 tonnes with a maximum graduation size of 0.5 kilograms. Cement shall be pre-weighed into a fabric container. The minimum amount of cement to be proportioned into any single container shall be one half of the total amount required for the load of RSC being produced.
4. Cement, water, and aggregate shall be proportioned volumetrically in conformance with these special provisions.

In order to check the accuracy of batch masses, the gross mass and tare mass of truck mixers shall be determined when ordered by the Engineer. The equipment shall be weighed at the Contractor's expense on scales designated by the Engineer.

The Contractor shall install and maintain in operating condition an electrically actuated moisture meter. The meter shall indicate, on a readily visible scale, changes in the moisture content of the fine aggregate as it is batched. The meter shall have a sensitivity of 0.5 percent by mass of the fine aggregate.

No additional mixing water shall be incorporated into the concrete during hauling or after arrival at the delivery point, unless authorized by the Engineer. If the Engineer authorizes additional water to be incorporated into the concrete, the drum shall be revolved not less than 30 revolutions at mixing speed after the water is added and before discharge is commenced. Water added to the truck mixer at the job site shall be measured through a meter that conforms to the provisions in Section 9-1.01, "Measurement of Quantities," of the Standard Specifications.

Aggregate discharged from several bins shall be controlled by gates or by mechanical conveyors. The means of discharge from the bins and from the weigh hopper shall be interlocked so that no more than one bin can discharge at a time, and so that the weigh hopper can not be discharged until the required quantity from each of the bins has been deposited in the weigh hopper.

### **Weighmaster Certificates**

Weighmaster certificates for RSC, regardless of the proportioning method used, shall include all information necessary to trace the manufacturer, and manufacturer's lot number for the cement being used. When proportioned into fabric containers the weighmaster certificates for the cement shall contain date of proportioning, location of proportioning and actual net draft mass of the cement. When proportioned at the pour site from a storage silo the weighmaster certificates shall contain date of proportioning, location of proportioning and the net draft mass of the cement used in the load.

### **Bond Breaker For Random Slab Replacement**

Bond breaker shall be placed between replacement pavement and existing lean concrete base, cement treated base or new base replacement layer. Bond breaker shall be one of the following:

1. Curing paper conforming to the requirements in ASTM Designation: C 171, white.
2. Polyethylene film conforming to the requirements in ASTM Designation: C 171, except that the minimum thickness shall be 0.15 mm, white opaque.
3. Paving asphalt, Grade PG 64-10, conforming to the provisions in Section 92, "Asphalts," of the Standard Specifications.
4. Pigmented curing compound conforming to the requirements in ASTM Designation: C 309, Type 2, Class A, containing a minimum of 22 percent nonvolatile vehicles consisting of at least 50 percent paraffin wax.

When curing paper or polyethylene film is used, material shall be placed in a wrinkle free manner. Adjacent sheets shall be overlapped a minimum of 150 mm.

When curing compound or paving asphalt is used, all foreign and loose materials remaining from slab removal shall be removed prior to application.

When paving asphalt is used, no water shall be added before applying asphalt to the surface of the base. The paving asphalt shall be applied in one even application at a rate of 0.10 to 0.45-L/m<sup>2</sup> over the entire base surface area. Concrete pavement shall not be placed until the paving asphalt has cured.

When curing compound is used, the curing compound shall be applied in two separate applications. Each application shall be applied evenly at a rate of 0.3 to 0.5-L/m<sup>2</sup> over the entire base surface area.

### **Spreading, Compacting and Shaping For Random Slab Replacement**

Spreading, compaction and shaping shall comply with Section 40 for lane replacement.

Metal or wood side forms may be used. Wood side forms shall not be less than 38-mm thick. Side forms shall be of sufficient rigidity, both in the form and in the connection with adjoining forms, that movement will not occur under the force from subgrading and paving equipment or from the pressure of concrete.

Side forms shall remain in place until the pavement edge no longer requires the protection of forms. Side forms shall be thoroughly cleaned and oiled prior to each use.

Consolidation of RSC shall be by means of high-frequency internal vibrators after the RSC is deposited on the subgrade. Vibrating shall be done in a manner to assure uniform consolidation adjacent to forms and across the full paving width. RSC shall be placed as nearly as possible in its final position and use of vibrators for extensive shifting of the mass of RSC will not be permitted.

RSC shall be spread and shaped by suitable powered finishing machines and supplemented by hand finishing as necessary. Methods of spreading, shaping and consolidating that result in segregation, voids or rock pockets shall be discontinued. The Contractor shall use methods that will produce dense homogeneous pavement conforming to the required cross section.

After the RSC has been mixed and placed, no additional water shall be added to the surface to facilitate finishing. Surface finishing additives, when used, shall be as recommended by the manufacturer of the cement and shall be approved by the Engineer prior to use.

### **Joints for Random Slab Replacement**

Prior to placing concrete against existing concrete, a 6-mm thick commercial quality polyethylene flexible foam expansion joint filler shall be placed across the original transverse and longitudinal joint faces and extend the full depth of the excavation. The top of the joint filler shall be placed flush with the top of pavement. Joint filler shall be secured to the joint face of the existing pavement by a method that will hold the joint filler in place during the placement of concrete.

Transverse weakened plane joints in pavement widenings shall be constructed to match the spacing and skew of the weakened plane joints in the adjacent existing pavement. Where the existing transverse weakened plane joint spacing in an adjacent lane exceeds 4.6 m, an additional transverse weakened plane joint shall be constructed midway between the existing joints. The provisions in the second and third paragraphs in Section 40-1.08B, "Weakened Plane Joints," and the third paragraph in Section 40-1.08B(1), "Sawing Method," of the Standard Specifications shall not apply. Sawing of weakened plane joints shall be completed within 2 hours of completion of final finishing. Minimum depth of cut for weakened plane joints shall be 100 mm.

Tie bars shall be deformed reinforcing steel bars conforming to the requirements in ASTM Designation: A 615/A 615M, Grade 280 or 420 and shall be epoxy-coated in conformance with the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications, except that references made to ASTM Designation: D 3963/D 3963M shall be deemed to mean ASTM Designation: A 934/A 934M or A 775/A 775M. Tie bars shall not be bent.

### **Epoxy (Drill and Bond)**

Epoxy for bonding tie bars and dowel bars to portland cement concrete shall be a two-component, epoxy-resin, conforming to the requirements of ASTM Designation: C 881, Type V, Grade 3 (Non-Sagging), Class A, B or C. The class used shall be dependent on the internal temperature of the hardened concrete at the time the epoxy is to be applied. Class A shall be used when the internal temperature is below 4°C, but not lower than recommended by the manufacturer. Class B shall be used when the internal temperature is from 4°C to 15°C. Class C shall be used when the internal temperature is above 15°C, but not higher than recommended by the manufacturer. A Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications shall be furnished with the epoxy. A copy of the manufacturer's recommended installation procedure shall be provided to the Engineer at least 7 days prior to the start of work. Epoxy shall be applied in conformance with the manufacturer's recommendations.

### **Dowel Bars**

Dowel bars shall be plain round smooth, epoxy-coated steel conforming to the requirements in ASTM Designation: A 615/A 615M, Grade 280 or 420, the details shown on the plans and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications, except that the two samples required in ASTM Designation D 3963/D 3963M shall be 460 mm long. Epoxy coating of dowel bars shall conform to the provisions in ASTM Designation: A 884/A 884M, Class A, Type 1 or Type 2, except that the bend test shall not apply.

Dowel bars shall be free from burrs or other deformations detrimental to free movement of the bars in the concrete.

### **Dowel Bar Bond Breaker**

Dowel bars shall be lubricated with a bond breaker over the entire bar. A bond breaker application of petroleum paraffin based lubricant or white-pigmented curing compound shall be used to coat the dowel bars completely prior to placement. Oil and asphalt based bond breakers shall not be used. Paraffin based lubricant shall be Dayton Superior DSC BB-Coat or Valvoline Tectyl 506 or an approved equal. Paraffin based lubricant shall be factory applied. White pigmented curing compound shall conform to the requirements of ASTM Designation: C 309, Type 2, Class A, and shall contain 22 percent minimum nonvolatile vehicles consisting of at least 50 percent paraffin wax. Curing compound shall be applied in 2 separate applications, the last application not more than 8 hours prior to placement of the dowel bars. Each application of curing compound shall be applied at the approximate rate of one liter per 3.7 m<sup>2</sup>.

### **Dowel Bar Baskets**

Dowel bar baskets shall be manufactured with a minimum welded wire gage number of MW 65. Baskets shall be either U-frame or A-frame shape. J-frame shapes shall not be used. Baskets shall be fabricated in conformance with the requirements in ASTM Designation: A 82. Welding of baskets shall conform to the requirements in AASHTO Designation: M 254. A broken weld will be a cause for rejection of the basket. Baskets shall be Class A, Type 1 or Type 2 epoxy-coated in conformance with the requirements in ASTM Designation: A 884/A 884M. Fabrication and job-site handling shall conform to the requirements in ASTM Designation: D 3963 and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications, except that sampling of epoxy-coated wire reinforcement will not be required. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished for each shipment of epoxy-coated wire reinforcement certifying that the coated bars conform to the requirements in ASTM Designation: A 884/A 884M and the provisions in Section 52-1.02B, "Epoxy-coated Bar Reinforcement," of the Standard Specifications. The Certificate of Compliance shall include the certifications specified in ASTM Designation:

Concrete fasteners shall be used for anchoring dowel bar baskets to lean concrete base, asphalt concrete base, asphalt treated permeable base, or cement treated permeable base. Concrete fasteners shall be driven fasteners such as nails, used specifically for fastening to hardened concrete, or asphalt concrete base. Concrete fasteners shall conform to the requirements of ASTM Designation: F 1667. Nails used as fasteners on lean concrete base or asphalt concrete base shall have a minimum shank diameter of 4 mm with a minimum shank length of 64 mm. Nails used as fasteners on asphalt treated or cement treated permeable base shall have a minimum shank diameter of 4 mm with a minimum shank length of 120 mm. Shank length shall be the distance from the point to the bottom of the nail head. Clips and washers shall be commercial quality manufactured for use with dowel bar baskets. The surface of concrete fasteners, clips, and washers shall be either zinc electroplated or galvanized with a minimum coating thickness of 0.005-mm.

### **Tie Bar Baskets**

Tie bar baskets shall be manufactured with a minimum welded wire gage number of MW 65. Baskets shall be either U-frame or A-frame shape. J-frame shapes shall not be used. Tie bar baskets shall be fabricated in conformance with the requirements in ASTM Designation: A 82. Welding of baskets shall conform to the requirements in AASHTO Designation: M 254. A broken weld will be a cause for rejection of the basket. Baskets shall be Class A, Type 1 or Type 2 epoxy-coated in conformance with the requirements in ASTM Designation: A 884/A 884M. Fabrication and job-site handling shall conform to the requirements in ASTM Designation: D 3963 and the provisions in Section 52-1.02B, "Epoxy-coated Reinforcement," of the Standard Specifications, except that sampling of epoxy-coated wire reinforcement will not be required. A Certificate of Compliance conforming to the provisions in Section 6-1.07, "Certificates of Compliance," shall be furnished for each shipment of epoxy-coated wire reinforcement certifying that the coated bars conform to the requirements in ASTM Designation: A 884/A 884M and the provisions in Section 52-1.02B, "Epoxy-coated Bar Reinforcement," of the Standard Specifications. The Certificate of Compliance shall include the certifications specified in ASTM Designation:

Concrete fasteners shall be used for anchoring tie bar baskets to lean concrete base, asphalt concrete base, asphalt treated permeable base, or cement treated permeable base. Concrete fasteners shall be driven fasteners such as nails, used specifically for fastening to hardened concrete, or asphalt concrete base. Concrete fasteners shall conform to the requirements of ASTM Designation: F 1667. Nails used as fasteners on lean concrete base or asphalt concrete base shall have a minimum shank diameter of 4 mm with a minimum shank length of 64 mm. Nails used as fasteners on asphalt treated or cement treated permeable base shall have a minimum shank diameter of 4 mm with a minimum shank length of 120 mm. Shank length shall be the distance from the point to the bottom of the nail head. Clips and washers shall be commercial quality manufactured for use with tie bar baskets. The surface of concrete fasteners, clips, and washers shall be either zinc electroplated or galvanized with a minimum coating thickness of 0.005-mm.

## Reinforcement

Reinforcement shall be epoxy coated and shall conform to the provisions in Section 52, "Reinforcement," of the Standard Specifications.

## Silicone Joint Sealant

Low modulus silicone joint sealant shall be furnished in a one-part silicone formulation. Acid cure sealant shall not be used. The compound shall be compatible with the surface to which it is applied and shall conform to the following requirements:

Property	Test Method	Requirement
Tensile stress, 150% elongation, 7-day cure at 25° ± 1°C and 45% to 55% R.H. <sup>e</sup>	ASTM D 412 (Die C)	310 kPa max.
Flow at 25° ± 1°C	ASTM C 639 <sup>a</sup>	Shall not flow from channel
Extrusion Rate at 25° ± 1°C	ASTM C 603 <sup>b</sup>	75-250 g/min.
Specific Gravity	ASTM D 792 Method A	1.01 to 1.51
Durometer Hardness, at -18°C, Shore A, cured 7 days at 25° ± 1°C	ASTM C 661	10 to 25
Ozone and Ultraviolet Resistance, after 5000 hours	ASTM C 793	No chalking, cracking or bond loss
Tack free at 25° ± 1°C and 45% to 55% R.H. <sup>e</sup>	ASTM C 679	Less than 75 minutes
Elongation, 7 day cure at 25° ± 1°C and 45% to 55% R.H. <sup>e</sup>	ASTM D 412 (Die C)	500 percent min.
Set to Touch, at 25° ± 1°C and 45% to 55% R.H. <sup>e</sup>	ASTM D 1640	Less than 75 minutes
Shelf Life, from date of shipment	—	6 months min.
Bond, to concrete mortar-concrete briquettes, air cured 7 days at 25° ± 1°C	AASHTO T 132 <sup>c</sup>	345 kPa min.
Movement Capability and Adhesion, 100% extension at -18°C after, air cured 7 days at 25° ± 1°C, and followed by 7 days in water at 25° ± 1°C	ASTM C 719 <sup>d</sup>	No adhesive or cohesive failure after 5 cycles

### Notes:

- ASTM Designation: C 639 Modified (15 percent slope channel A).
- ASTM Designation: C 603, through 3-mm opening at 345 kPa.
- Mold briquettes in conformance with AASHTO Designation: T 132, sawed in half and bonded with a 1.5 mm maximum thickness of sealant and tested in conformance with AASHTO Designation: T 132. Briquettes shall be dried to constant mass at 100 ± 5° C.
- Movement Capability and Adhesion: Prepare 305 mm x 25 mm x 75 mm concrete blocks in conformance with ASTM Designation: C 719. A sawed face shall be used for bond surface. Seal 50 mm of block leaving 12.5 mm on each end of specimen unsealed. The depth of sealant shall be 9.5 mm and the width 12.5-mm.
- R.H. equals relative humidity.

The silicone joint sealant shall be formulated to cure rapidly enough to prevent flow after application on grades of up to 15 percent.

A Certificate of Compliance for the silicone sealant shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The Certificate shall also be accompanied with a certified test report of the results of the required tests performed on the sealant material within the previous 12 months prior to proposed use. The Certificate and accompanying test report shall be provided for each lot of silicone joint sealant prior to use on the project.

### **Foam Backer Rods**

Foam backer rods shall be Type 1, conforming to the requirements of ASTM Designation: D 5249. Foam backer rods shall have a diameter prior to placement at least 25 percent greater than the width of the sawcut and shall be expanded, crosslinked, closed-cell polyethylene foam that is compatible with the joint sealant so that no bond or adverse reaction occurs between the rod and sealant. Hot applied sealant that will melt the foam backer rod shall not be used. The Contractor shall submit a manufacturer's data sheet verifying that the foam backer rod is compatible with the sealant to be used.

Joint filler material shall be Type 2 preformed expansion joint filler for concrete conforming to the requirements of ASTM Designation: D 1752.

A Certificate of Compliance for the joint filler material shall be furnished to the Engineer in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications. The certificate shall be accompanied with a certified test report of the results of the required tests performed on the joint filler material within the previous 12 months prior to proposed use. The certificate and accompanying test report shall be provided for each lot of joint filler material prior to use on the project.

### **Hydraulic Cement Grout (non-shrink)**

Hydraulic cement grout (non-shrink) shall conform to the requirements in ASTM Designation: C 1107. At the Contractor's option, clean, uniformly rounded aggregate filler may be used to extend the grout. The extension of grout shall not exceed 60 percent of the mass of the grout or the maximum amount of grout extension recommended by the manufacturer, whichever is less. The moisture content of the aggregate filler shall not exceed 0.5 percent. Grading of the aggregate filler shall conform to the following:

Sieve Size	Percentage Passing
12.5 mm	100
9.5 mm	85-100
4.75 mm	10-30
2.36 mm	0-10
1.10 mm	0-5

### **INSTALLING TIE BARS**

Tie bars shall be installed at longitudinal contact joints and longitudinal weakened plane joints as shown on the plans. Contiguous width of concrete pavement tied together with tie bars shall not exceed 15 m. Tie bars shall not be installed at joints between RSC and asphalt concrete pavements.

Tie bars shall be installed at longitudinal joints by one of the following methods:

1. Drilling and bonding tie bars with two-component, epoxy-resin that conforms to this section. Drilled holes shall be cleaned in conformance with the epoxy manufacturer's instructions and shall be dry at the time of placing the epoxy and tie bars. Tie bars will be rotated 180° while being inserted into the epoxy filled holes. Immediately after inserting the tie bars into the epoxy, the tie bars shall be supported as necessary to prevent movement during curing and shall remain undisturbed until the epoxy has cured as specified by the manufacturer instructions. Tie bars that are improperly placed or bonded, as determined by the Engineer, will be rejected. If rejected, new holes shall be drilled and new tie bars shall be placed and securely bonded to the concrete. Rejected tie bars shall be cut flush with the joint face. Exposed ends of tie bars shall be epoxy coated. The center of the new holes shall be offset 75 mm horizontally from the center of the rejected hole to maintain the minimum clearance to the dowel bar. Work necessary to correct improperly bonded tie bars shall be performed at the Contractor's expense.
2. Inserting tie bars into the plastic slipformed concrete before finishing the concrete. Inserted tie bars shall have full contact between the bar and the concrete. When tie bars are inserted through the pavement surface, the concrete over the tie bars shall be reworked and refinished so that there is no evidence on the surface of the completed pavement that there has been an insertion performed. Loose tie bars shall be replaced by drilling and bonding as described in A above, at the Contractor's expense.
3. Using threaded dowel splice couplers fabricated from deformed bar reinforcement material, free of external welding or machining. Threaded dowel splice couplers shall be accompanied by a Certificate of Compliance in conformance with the provisions in Section 6-1.07, "Certificates of Compliance," of the Standard Specifications, and shall be accompanied with installation instructions. Installation of threaded dowel splice couplers shall conform to the requirements of the manufacturer's recommendations.
4. Using tie bar baskets that conform to these special provisions

Tie bars shall be oriented perpendicular to the pavement joint and parallel with the surface of the pavement at mid-slab depth. Tie bar alignment tolerances shall conform to the requirements for dowel bars except embedment length tolerance shall be  $\pm 50$  mm.

If tie bar baskets are used, they shall be anchored to the base to hold the tie bars at the specified depth and alignment during concrete placement without displacement. A minimum of 8 alternating, equally spaced, concrete fasteners with clips shall be used to anchor each basket (4 per lower runner wire). Temporary spacer wires shall be cut or removed after the baskets are anchored into position before concrete placement. Concrete pavement shall not be placed if the baskets are not in place at least 60 m in advance of the concrete placement operation. The Engineer may waive this requirement upon written request by the Contractor in areas where access is restricted or other construction limitations are encountered. The Contractor shall demonstrate that the baskets are anchored and shall not shift during concrete placement. The Contractor shall provide longer concrete nails than the minimum lengths for the varying bases beneath the RSC when baskets demonstrate movement.

Full compensation for providing longer nails shall be considered as included in the contract unit price paid per cubic meter for concrete pavement and no additional compensation will be allowed therefor.

### DOWEL PLACEMENT

Dowel bars shall be centered on the joint within a tolerance of  $\pm 50$  mm in the longitudinal direction directly over the contact joint or sawcut for the transverse weakened plane joints, as shown on the plans. Prior to placement of dowel bars, the Contractor shall submit to the Engineer a written procedure to identify the transverse weakened plane joint locations relative to the middle of the dowel bars and the procedure for consolidating concrete around the dowel bars.

Dowel bars shall be placed at transverse weakened plane joints within shoulder areas except at drainage inlets.

Dowel bars shall be placed as shown on the plans by using dowel bar baskets or by mechanical insertion.

When dowel bars are placed by mechanical insertion, the concrete over the dowel bars shall be reworked and refinished so that there is no evidence on the surface of the completed pavement that there has been any insertion performed. When drill and bonding of dowel bars is performed at contact joints, a grout retention ring shall be used. When dowel bar baskets are used, they shall be anchored to the base to hold the dowel bars at the specified depth and alignment during concrete placement without displacement. A minimum of 8 alternating, equally spaced, concrete fasteners with clips shall be used to anchor each 3.6 m dowel bar basket (4 per lower runner wire). At least 10 concrete fasteners shall be used for basket sections greater than 3.6 m and less than or equal to 4.9 m. Temporary spacer wires connecting dowel bar baskets shall be cut or removed after the dowel bar baskets are anchored into position prior to concrete placement. Paving shall be suspended when dowel bar baskets are not in place at least 60 m in advance of the concrete placement operation. The Engineer may waive this requirement upon written request by the Contractor, in areas, where access is restricted, or other construction limitations are encountered. The Contractor shall demonstrate to the Engineer's satisfaction that dowel bar baskets are adequately anchored and not shift during concrete placement. The Contractor shall provide longer concrete nails than the minimum lengths for the varying bases beneath the RSC when anchored dowel bar baskets demonstrate movement.

Full compensation for providing longer nails shall be considered as included in the contract unit price paid per cubic meter for concrete pavement and no additional compensation will be allowed therefor.

Dowel bar placement at transverse and longitudinal weakened plane joints	
Horizontal offset	$\pm 25$ mm
Longitudinal translation	$\pm 50$ mm
Horizontal skew	9 mm
Vertical skew	9 mm
Vertical depth	( $d/3 + 12$ mm) from pavement surface to top of dowel bar or $-15$ mm below planned placement

Note:  $d$  = pavement thickness in mm

## **CORE DRILLING FOR DOWEL BAR AND TIE BAR PLACEMENT ALIGNMENT ASSURANCE TESTING**

Coring to confirm dowel bar and tie bar placement, alignment, and concrete consolidation shall be provided by the Contractor throughout the project, at locations determined by the Engineer. Each day's paving shall be cored within 2 days by performing a minimum of 2 and a maximum of 4 tests for dowel bar placement and position for every 1670 m<sup>2</sup> of doveled pavement or fraction thereof and one test for tie bar placement and position for every 3340 m<sup>2</sup> of pavement with tie bars. One test shall consist of drilling two cores, one on each end of a dowel bar to expose both ends and allow measurement for proper alignment. The minimum core hole diameter shall be 127 mm. If the cores indicate that dowel bars or tie bars are not within the allowable tolerances or if air voids exist surrounding the dowel bars or tie bars, additional cores will be required to determine the limits and severity of unacceptable work.

The holes shall be cored by methods that will not damage the concrete adjacent to the holes. Immediately after coring, the concrete cores shall be submitted to the Engineer for inspection, and the cores shall be identified by the Contractor with a location description.

After removal of cores, core hole voids in concrete pavement shall be cleaned and filled with hydraulic cement grout (non-shrink). After placement of hydraulic cement grout, the material while still plastic shall be finished and textured to match the adjacent pavement surface. The backfill material shall be the same level as the pavement surface.

Water for core drilling operations shall be from a local domestic water supply, and shall contain not more than 1000 parts per million of chlorides as CL, nor more than 1300 parts per million of sulfates as SO<sub>4</sub>, nor shall it contain impurities in a sufficient amount to cause discoloration of the concrete or produce etching of the surface.

Water from core drilling operations shall not be permitted to fall on public traffic, to flow across shoulders or lanes occupied by public traffic, or to flow into gutters or other drainage facilities.

Dowel bar and tie bar alignment shall be within the specified tolerances. If dowel bars or tie bars are found to be installed improperly, the paving operations shall not continue until the Contractor has demonstrated to the Engineer that the problem which caused the improper dowel bar or tie bar positioning has been corrected.

Dowel bars in rejected joints shall be replaced by the Contractor by saw cutting on each side of the rejected joint a minimum of 0.9-m, lifting out concrete to be removed, installing new dowel bars at the new transverse joints, installing dowel bars and preformed sponge rubber expansion joint filler along the longitudinal joints, placing concrete, and installing new joints. Preformed sponge rubber expansion joint filler shall conform to the requirements in ASTM Designation: D 1752. New dowel bar holes shall be drilled, not more than 3 mm greater than the dowel bar diameter, by the use of an automatic dowel-drilling rig for the dowels to be installed at the contact joints. Dowel bars shall be placed, as shown on the plans, for the 2 new transverse contact joints. Original exposed tie bars, located within the slab replacement area, shall be cut flush with the lane or pavement edge and dowel bars shall be installed to replace the tie bars at an offset of 75 mm, horizontally from the tie bar location. Holes for dowel bars to be placed along the longitudinal joint shall be drilled, not more than 3 mm greater than the dowel bar diameter, by the use of an automatic dowel-drilling rig for the dowel bars to be installed at the contact joints.

When requested by the Contractor and approved by the Engineer, dowel bars which are more than ±50 mm but less than ±75 mm from being centered directly over the sawcut for the transverse weakened plane joint, may remain in place, and the Contractor shall pay to the State the amount of \$32.30 per square meter for the quantity of concrete pavement panels represented by the cores indicating incorrect dowel bar alignment or improper concrete consolidation around dowels. The quantity of concrete pavement area used to determine the amount of payment to the State will be calculated using the panel dimensions for panels adjacent to and inclusive of the joints with incorrect dowel bar alignment or improper concrete consolidation around dowel bars. The Department will reduce compensation from moneys due, or that may become due to the Contractor under the contract. This reduced compensation shall be in addition to other adjustments for incorrect tie bar alignment or improper concrete consolidation around tie bars as specified in these special provisions and for pavement thickness deficiency in conformance with the provisions in Section 40-1.135, "Pavement Thickness," of the Standard Specifications and in addition to other adjustments for deficient Cleaness Value and coarse aggregate grading; and for deficient Sand Equivalent and fine aggregate grading in conformance with the provisions in Section 90-2.02, "Aggregate," of the Standard Specifications.

Tie bars which are not within the specified tolerance for placement and position, as determined from inspection and measurements of cores, may remain in place when requested by the Contractor and approved by the Engineer. The Contractor shall pay to the State the amount of \$16.15 per square meter for the quantity of concrete pavement panels represented by the cores indicating incorrect tie bar alignment or improper concrete consolidation around tie bars. The quantity of concrete pavement area used to determine the amount of payment to the State will be calculated using the panel dimensions for panels adjacent to and inclusive of the joints with incorrect tie bar alignment or improper concrete consolidation around tie bars. The Department will reduce compensation from moneys due, or that may become due to the Contractor under the contract. This reduced compensation will be in addition to other adjustments for incorrect dowel bar alignment or improper concrete consolidation around dowel bars as specified in these special provisions and for pavement thickness deficiency in conformance with the provisions in Section 40-1.135, "Pavement Thickness," of the Standard Specifications and in addition to other adjustments for deficient Cleanness Value and coarse aggregate grading; and for deficient Sand Equivalent and fine aggregate grading in conformance with the provisions in Section 90-2.02, "Aggregate," of the Standard Specifications.

### **LIQUID JOINT SEALANT INSTALLATION**

The joint sealant detail for transverse and longitudinal joints, as shown on the plans, shall apply only to weakened plane joints. Weakened plane joints shall be constructed by the sawing method. Should grinding or grooving be required over or adjacent to joints after sealant has been placed, the joint materials shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications, and replaced at the Contractor's expense. Immediately after sawing, a water wash using less than 0.7 MPa pressure shall be used to remove the slurry from the sawing operation.

Transverse weakened plane joints shall be Type A1 or B as shown on the plans. Longitudinal weakened plane joints shall be Type A2 or B as shown on the plans.

Seven days after the concrete pavement placement and not more than 4 hours before placing backer rods and joint sealant materials, the joint walls shall be cleaned by the dry sand blast method and other means as necessary to remove from the joint objectionable material such as soil, asphalt, curing compound, paint and rust. Sand blasting shall be performed in at least 2 passes, one for each side of the joint, with the nozzle held at an angle to the joint within 25 to 51 mm of the pavement. After cleaning the joint, traces of sand, dust and loose material shall be removed from and near the joint for a distance along the pavement surfaces of at least 50 mm on each side of the joint by the use of a vacuum device. Surface moisture or dampness shall be removed at the joints by means of compressed air or moderate hot compressed air or other means approved by the Engineer. Drying procedures that leave a residue or film on the joint wall shall not be used. Sandblasting equipment shall have a maximum nozzle diameter size of  $6 \pm 1$ -mm and a minimum pressure of 0.62-MPa.

Backer rods shall be installed when the temperature of the concrete pavement is above the dew point of the air and when the air temperature is 4°C or above. Backer rod shall be installed when the joints to be sealed have been properly patched, cleaned and dried, as determined by the Engineer. Methods of placing backer rod that leave a residue or film on joint walls shall not be used.

Immediately after placement of the backer rod, joint sealant shall be placed in the clean, dry, prepared joints as shown on the plans. The joint sealant shall be applied using a mechanical device with a nozzle shaped to fit inside the joint to introduce the sealant from inside the joint. Adequate pressure shall be applied to the sealant to ensure that the sealant material is extruded evenly and that full continuous contact is made with the joint walls. After application of the sealant, the surface of the sealant shall be recessed as shown on the plans.

Failure of the joint material in either adhesion or cohesion will be cause for rejection of the joint. The finished surface of joint sealant shall conform to the dimensions and allowable tolerances shown on the plans. Rejected joint materials or joint material whose finished surface does not conform to the dimensions shown on the plans, as determined by the Engineer, shall be repaired or replaced, at the Contractor's expense, with joint material that conforms to the requirements.

After each joint is sealed, surplus joint sealer on the pavement surface shall be removed. Traffic shall not be permitted over the sealed joints until the sealant is tack free and set sufficiently to prevent embedment of roadway debris into the sealant.

### **CONSTRUCTING TRANSVERSE CONTACT JOINTS**

A transverse contact (construction) joint shall be constructed, including dowel bars, at the end of each day's work or where concrete placement is interrupted for more than minutes, to coincide with the next weakened plane joint location.

If sufficient concrete has not been mixed to form a slab to match the next weakened plane joint, when an interruption occurs, the excess concrete shall be removed and disposed of back to the last preceding joint. The cost of removing and disposing of excess concrete shall be at the Contractor's expense. Excess material shall become the property of the Contractor and shall be disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

A metal or wooden bulkhead (header) shall be used to form the joint. The bulkhead shall be designed to accommodate the installation of dowel bars.

### **CONSTRUCTING LONGITUDINAL ISOLATION JOINTS (LANE REPLACEMENT)**

Final alignment of perpendicular transverse weakened plane joints in pavement shall not be made to match the spacing or skew of the weakened plane joints in the existing parallel concrete pavement. Tie bars shall not be placed across longitudinal isolation joints. The edge of the existing pavement shall be saw cut a width 3 mm and to the full depth of the existing concrete pavement to produce a flat vertical face. Prior to placing concrete, joint filler material shall be placed as shown on the plans. The joint filler shall be secured to the face of the existing pavement joint face by a method that will hold the joint filler in place and prevent the new concrete from adhering to the existing concrete, during placement of concrete.

Sealant for longitudinal isolation joints shall be silicone joint sealant and placed in conformance with the requirements for liquid joint sealant installation as specified above, except references to backer rods shall not apply.

### **CONSTRUCTING TRANSVERSE JOINT CONNECTIONS AND ANCHORS**

Concrete pavement joints at transitions to asphalt concrete pavement, pavement end anchors and bridge approach slabs shall conform to the details as shown on the plans. Paint binder shall be applied to the concrete surface that asphalt concrete pavement will contact. Paint binder shall be applied in conformance with the provisions in Section 39, "Asphalt Concrete," of the Standard Specifications.

### **PROFILE INDEX**

The pavement surface shall be profiled, by the Contractor not more than 10 days following concrete placement, in the presence of the Engineer, using a California Profilograph or equivalent in conformance with the requirements in California Test 526, except a blanking band of zero (null) shall be used to determine the Profile Index. Two profiles shall be made within each traffic lane, one meter from and parallel with each lane line.

Profiled pavement shall conform to the following Profile Index requirements:

- A. Pavement on tangent alignment and pavement on horizontal curves having a centerline radius of curve 600 m or more shall have a Profile Index of 64 mm or less for each 0.1-km.
- B. Pavement on horizontal curves having a centerline radius of curve 300 m or more but less than 600 m and pavement within the superelevation transition of those curves shall have a Profile Index of 128 mm or less for each 0.1-km.

Concrete shoulders shall be profiled. Two profiles shall be made within the shoulder, one meter from and parallel with each edge of the shoulder. Concrete shoulders profiled shall conform to the Profile Index requirements in this section.

Individual high points in excess of 7.5 mm, as determined by measurements of the profilogram in conformance with the requirements in California Test 526, except using a blanking band of zero (null), shall be reduced by grinding in conformance with the requirements in Section 40-1.10, "Final Finishing," of the Standard Specifications until the high points as indicated by reruns of the profilograph do not exceed 7.5 mm.

Pavement grinding shall not be performed before 10 days have elapsed after concrete placement, nor before the concrete has developed a modulus of rupture of at least 3.8 MPa.

### **Final Finishing**

Tests to determine coefficient of friction of the final textured surface will be made only if the Engineer determines by visual inspection that the final texturing may not have produced a surface having the specified coefficient of friction. Any tests to determine the coefficient of friction will be made after the pavement is opened to public traffic, but not later than 5 days after concrete placement. Pavement areas having a coefficient of friction as determined in conformance with the requirements in California Test 342 of less than 0.30 shall be grooved in conformance with the provisions in Section 42-1.02, "Construction," of the Standard Specifications. Grooving shall be performed prior to the installation of any required edge drains adjacent to the areas to be grooved.

Transverse straightedge and longitudinal straightedge requirements will not apply to the pavement surface within 300 mm of the existing concrete pavement except as required in these special provisions. Longitudinal straightedge requirements in Section 40-1.10, "Final Finishing," of the Standard Specifications, shall be applied at transverse contact joints with existing concrete pavement where the straightedge is to be placed with the midpoint coincident with the joints. Pavement not meeting this straightedge requirement shall be corrected within 48 hours by grinding or other methods as approved by the Engineer.

### **Curing Method**

The curing method for replacement pavement shall be as recommended by the manufacturer of the cement and as approved by the Engineer.

## **QUALITY CONTROL PROGRAM**

### **General**

The Contractor shall establish, provide and maintain a quality control program that will provide assurance to the Engineer that all materials and completed construction conform to the contract requirements specified herein.

At least 20 days prior to the placement of the trial slab the Contractor shall submit to the Engineer for approval a written Quality Control Plan (QCP) that shall be used to ensure the quality of the product and the work. At the request of the Engineer or Contractor, the Contractor and Quality Control Managers (QCMs) shall meet with the Engineer to discuss the QCP. The Engineer will have 15 days to approve the Quality Control Plan (QCP). Should the Engineer fail to complete the review of the Quality Control Plan (QCP) within the time allowance and if, in the opinion of the Engineer, the Contractor's controlling operation is delayed or interfered with by reason of the delay in reviewing the Quality Control Plan (QCP), the delay will be considered a right of way delay in conformance with the provisions in Section 8-1.09, "Right of Way Delays," of the Standard Specifications.

If in the judgement of the Engineer, the Contractor has not implemented or is not complying with the approved QCP, production and placement shall be suspended. Production and placement shall not resume until approved by the Engineer.

### **Quality Control Plan**

The Contractor shall provide a QCP that describes the procedures that the Contractor will use to control the production process, to determine when changes to the production process are needed, and to propose procedures for implementing changes for replacement pavement operations. The QCP shall also include an outline for the placement and testing of the trial slab.

Replacement pavement production and placement shall not begin until the QCP has been approved by the Engineer. Approval of the QCP will be based on the inclusion of all required information. Approval of the QCP does not imply any warranty by the Engineer that adherence to the QCP will result in replacement pavement that complies with these specifications. It shall remain the responsibility of the Contractor to demonstrate this compliance.

The QCP shall include the names and qualifications of the lead QCM and the assistant QCM. The lead QCM shall be responsible for the administration of the QCP. The lead QCM shall have current American Concrete Institute (ACI) certification as "Concrete Field Testing Technician-Grade I" and "Concrete Laboratory Testing Technician-Grade II." The assistant QCM shall have current ACI certification as "Concrete Field Testing Technician-Grade I" and either "Concrete Laboratory Testing Technician-Grade I" or "Concrete Laboratory Testing Technician-Grade II." All sampling, inspection and test reports shall be reviewed and signed by the QCM responsible for the production period involved prior to submittal to the Engineer. At least one QCM shall be present for each stage of mix design, trial slab construction, during production and construction of replacement pavement and for all meetings between the Contractor and Engineer relating to production, placement or testing of replacement pavement. The QCMs shall not be members of production or paving crews, inspectors or testers on the project during production or placement of replacement pavement. QCMs shall have no duties other than those referenced in these special provisions during the production and placement of replacement pavement.

The QCP shall include an outline of the production, transportation and placement of the replacement pavement. The QCP shall include a contingency plan for correcting situations if there is a problem in production, transportation or placement. The Contractor shall have equipment and personnel present to meet the requirements of the contingency plan. The QCP shall contain provisions for determining when placement of the replacement pavement will be suspended and temporary roadway will be substituted.

The QCP shall include the names of quality control personnel to be used and an outline of sampling, testing to be performed during and after construction of replacement pavement. At the time of submission of the QCP, quality control samplers and testers must be Caltrans qualified by the Department through the Independent Assurance Program (IAP) for the sampling and testing for which they will be responsible.

Before production and placement begins, the Contractor, QCMs and Engineer shall have a meeting with all production, transportation, placement, inspection, sampling and testing personnel to familiarize them with the requirements of the project. Items to be discussed include the production, transportation and placement processes for replacement pavement; contingency plan; and sampling and testing. The Contractor shall provide the facility for this meeting. The meeting date and location will be approved by the Engineer. Attendance at this meeting is mandatory for key personnel including the project manager, QCMs, production plant manager, plant inspector, all concrete delivery truck drivers, paving superintendent, paving foreman, paving machine operator, and all inspectors, samplers and testers. All meeting attendees shall sign in at the meeting. Production and placement operations shall not begin unless the above key personnel have attended the mandatory meeting.

### **Quality Control Inspection, Sampling and Testing**

The Contractor shall perform quality control inspection, sampling and testing to ensure that replacement pavement production and placement conform to the provisions specified herein.

The Contractor shall provide the required sampling, testing and inspection during all phases of replacement pavement production and placement. The Contractor shall provide a minimum of two working days notice to the Engineer, so the Engineer can witness all sampling and testing. The Engineer shall be given unrestricted access to the Contractor's quality control inspectors, samplers, testers and laboratories. During the production and placement period, the Contractor shall provide results of all testing to the Engineer within 15 minutes of completion of testing. The Contractor shall record all inspection, sampling and testing on forms approved by the Engineer. The Contractor shall provide written results of all inspection and testing to the Engineer within 48 hours of completion of each shift of paving and within 24 hours for all 7-day strength tests.

The Contractor shall provide a testing laboratory with adequate equipment and personnel for the performance of the quality control tests. This laboratory shall be located at a location approved by the Engineer and so that prompt testing requirements will be achieved. All sampling and testing equipment shall be maintained in proper working condition. Sampling shall be performed in conformance with the requirements of California Test 125. The QCP shall include a list the equipment to be used including date of last calibration, the names and certifications of sampling and testing personnel, and the location of the laboratory and testing equipment during and after paving operations.

Testing laboratories, testing equipment, and sampling and testing personnel shall conform to the requirements of the Department's IAP.

### **Trial Slab and Process Control Testing**

Prior to construction of RSC pavement, the Contractor shall construct one or more trial slabs under conditions similar to those that will exist during pavement replacement, for each mix design, to show that personnel, equipment, and mixing, placing, curing, and sawing techniques will produce a concrete pavement conforming to these special provisions in the anticipated time period under similar atmospheric and temperature conditions as pavement construction and to establish the correlation described below. During production and placement, the Contractor shall conform to the requirements of these special provisions and to the procedure outlined in the QCP to ensure that mixing, transporting, placing, finishing, curing and sawing techniques and that personnel and equipment to be used will produce replacement pavement conforming to these special provisions.

A trial slab shall be constructed using the approved mix design, admixtures and conditions for batching. During construction of trial slab, the Contractor shall demonstrate placement at the minimum and maximum times allowed from batching to placement. RSC pavement within the roadway shall not proceed until a trial slab meeting the requirements of these special provisions has been constructed.

The minimum trial slab dimensions shall be 3 m by 6 m and shall be 225 mm thick where planned replacement pavement nominal thickness is less than 255 mm. The trial slab thickness shall be 260 mm where planned replacement pavement nominal thickness is 255 mm or greater. Where there are planned slab replacements with greater and less than 255 mm thickness then two trial slabs shall be required one at 225 mm thick and one at 255 mm thick. Trial slabs shall be placed near the project site at a location mutually acceptable to the Engineer and the Contractor except slabs shall not be placed on the roadway or within the project limits.

During trial slab construction, the Contractor shall sample and split the aggregate for gradings, cleanness value, and sand equivalent testing with the Engineer, at the Contractor's cost. Both sets of test results of these samples shall conform to the provisions in Section 90-2.02, "Aggregates," of the Standard Specifications. If test results do not conform to the requirements, the trial slab will be rejected.

During trial slab construction and within 20 minutes of RSC delivery, beams shall be fabricated in conformance with the requirements in California Test 523. Beams shall be used to determine early age and 7-day modulus of rupture values. Beams fabricated for early age testing shall be cured so that the monitored temperature in the beams and the trial slab are within 3°C at all times. Internal temperatures of the trial slab and early age beams shall be monitored and recorded at minimum time intervals of 5 minutes by installing thermocouples and or thermistors connected to strip-chart recorders or digital data loggers. Temperature recording devices shall be accurate to within  $\pm 1^\circ\text{C}$ . Internal temperature readings shall be measured at 25 mm from the top and 25 mm from the bottom, no closer than 75 mm from any edge of the concrete elements, until the early age testing is completed. Beams fabricated for 7-day testing shall be cured in conformance with the requirements in California Test 523, except beams shall be placed into sand at between 5 and 10 times the final set time or 24 hours, whichever is earlier. Testing shall be performed by the Contractor and witnessed by the Engineer. At the Engineer's request, the Contractor shall produce samples for the Engineer to test. Strength results from beams shall be the basis for determining whether RSC pavement operations may proceed. Trial slabs 225 mm thick shall have an early age modulus of rupture of not less than 2.8 MPa and a 7-day modulus of rupture of not less than 4.2 MPa. Trial slabs 260 mm thick shall have an early age modulus of rupture of not less than 2.3 MPa and a 7-day modulus of rupture of not less than 4.2 MPa. Beams failing early age or 7-day modulus of rupture requirements shall be cause for the rejection of the trial slab.

When proposed by the Contractor, in writing, and approved by the Engineer, ASTM Designation: C 805 or C 900 shall be used to estimate the modulus of rupture of the pavement at early ages. The selected test method shall be used to determine modulus of rupture until 7 days after the Contractor notifies the Engineer of withdrawal of the proposal or 7 days after the Engineer notifies the Contractor of withdrawal of approval, in writing. During trial slab curing, correlation testing shall be performed to determine the relation between the modulus of rupture and ASTM Designation: C 805 or C 900 performed on the trial slab. The correlation shall be established by testing at 4 or more time intervals. At a minimum, tests shall be performed one hour before and one hour after the opening age and two others within 15 minutes of the opening age. Modulus of rupture estimates shall be calculated with either a linear, exponential or logarithmic, least squares best-fit equation, whichever provides the best correlation coefficient.

The Contractor shall state in detail the intended location and time; procedure for production, placement and finishing of RSC pavement; sampling, sample curing and sample transportation; testing and reporting of test results for the trial slab in the QCP.

### **Process Control and Quality Control Testing**

The Contractor shall provide continuous process control and quality control sampling and testing throughout production and placement of replacement pavement.

During production of RSC for replacement pavement operations, the Contractor shall sample and test aggregates at least once every 500 cubic meters of RSC produced but not less than once per placement shift. Aggregates shall be tested for conformance with gradations, cleanness value and sand equivalent requirements.

During placement of RSC pavement, the Contractor shall fabricate specimens and test for modulus of rupture within the first 25 cubic meters, within the final truckload and at least once every 100 cubic meters.

During placement of RSC, the Contractor shall sample and test for yield, penetration, air content and unit weight at least once in every 500 cubic meters RSC produced but not less than twice per placement shift.

At the Engineer's request, the Contractor shall provide split samples and fabricate beams for the Engineer to test. The cost of sampling, fabricating and transporting extra samples will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications. When, in the opinion of the Engineer, RSC fails to conform to the mix design requirements or the requirements of these special provisions, the Contractor shall provide samples and testing at the direction of the Engineer. If the material fails to meet requirements of these special provisions, cost of sampling and testing shall be at the Contractor's expense. If the material meets the requirements of these special provisions, the cost of sampling and testing will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

Beams used for determining early age modulus of rupture shall be cured under the same conditions as the pavement until one hour prior to testing. Beams fabricated for the 7-day test shall be cured in conformance with California Test 523 as modified in these special provisions. Modulus of rupture test results will be used for accepting or rejecting the replacement pavement and pay factor adjustment for low modulus of rupture.

Materials resulting from the construction of the trial slab, test specimens, temporary roadway structural section, and all rejected replacement pavement shall become the property of the Contractor and shall be removed and disposed of in conformance with the provisions in Section 7-1.13, "Disposal of Material Outside the Highway Right of Way," of the Standard Specifications.

### **REPLACE EXISTING PAVEMENT DELINEATION**

Whenever existing pavement delineation is removed, obliterated or damaged due to the work involved in replacing concrete pavement, the Contractor shall replace the delineation in conformance with the requirements of these special provisions.

### **MEASUREMENT AND PAYMENT**

Replace concrete pavement (Rapid Strength Concrete) will be measured and paid for in the same manner specified for concrete pavement in Sections 40-1.13, "Measurement," and 40-1.14, "Payment," of the Standard Specifications, and these special provisions. No deduction will be made for the volume of epoxy-coated dowel bars, epoxy-coated tie bars and, when used, tie bar baskets with fasteners and dowel bar baskets with fasteners, in the concrete pavement.

Replace concrete pavement (Rapid Strength Concrete) payments will be subject to the pay factor values listed in "Pay Factor Adjustment for Low Modulus of Rupture" of these special provisions.

Sealing longitudinal and transverse weakened plane joints, and longitudinal isolation joints in portland cement concrete pavement will be measured by the meter. The contract price paid per meter for seal pavement joint shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in sealing pavement joints complete in place, including sawing, cleaning and preparing the joints in the concrete pavement, furnishing and installing backer rod, repairing and patching spalled or raveled sawed joints, and replacing or repairing rejected joints, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract price paid per meter for seal longitudinal isolation joint shall include full compensation for furnishing all labor, materials, tools, equipment, and incidentals, and for doing all the work involved in sealing longitudinal isolation joints complete in place, including sawing, cleaning and preparing the joints in the concrete pavement, furnishing and installing joint filler material, repairing and patching spalled or raveled sawed joints, and replacing or repairing rejected joints, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

The contract price paid per cubic meter for replace concrete pavement (Rapid Strength Concrete) shall include full compensation for furnishing all labor, materials (including cementitious material in the amount determined by the Contractor), tools, equipment, and incidentals, and for doing all the work involved in constructing the portland cement concrete pavement complete in place, including furnishing and placing epoxy-coated dowel bars, epoxy-coated tie bars and, when used, any tie bar baskets and dowel bar baskets with fasteners, submittal to the Engineer all test data for determination of mix proportions of concrete for concrete pavement, for constructing and repairing all joints; for performing all profile checks for Profile Index and furnishing final profilograms to the Engineer; for grooving and grinding required for final finishing; and for removing, and replacing pavement for deficient thickness, as shown on the plans, as specified in the Standard Specifications and these special provisions, and as directed by the Engineer.

Full compensation for the pre-operation conference, including furnishing the facility to hold the pre-operation conference in, shall be considered as included in the contract prices paid for the item involving RSC and no additional compensation will be made therefor.

Costs for providing JITT will be made in conformance with the provisions in Section 9-1.03, "Force Account Payment," of the Standard Specifications, except no markups shall be added, and the Contractor will be paid for one half of the JITT cost. Costs for providing JITT shall include training materials, class site, and the JITT instructor including the JITT instructor's travel, lodging, meals and presentation materials. All costs incurred by the Contractor or Engineer for attending JITT shall be borne by the party incurring the costs.

Full compensation for core drilling for dowel bar or tie bar alignment and backfilling with hydraulic cement grout shall be considered as included in the contract price per cubic meter for concrete pavement and no additional compensation will be allowed therefor.

If the initial cores show that dowel bars or tie bars are out of alignment tolerances and the Engineer orders additional dowel bar or tie bar coring, full compensation for drilling the additional cores shall be considered as included in the contract price per cubic meter for concrete pavement and no additional compensation will be allowed therefor.

If the initial cores show that dowel bars or tie bars are within alignment tolerances and the Engineer orders more dowel bar coring the additional cores will be paid for as extra work in conformance with the provisions in Section 4-1.03D, "Extra Work," of the Standard Specifications.

The provisions in Section 40-1.135, "Pavement Thickness," of the Standard Specifications shall not apply for random slab replacement.

Full compensation for removing and disposing of existing concrete pavement, constructing trial slabs, furnishing and placing bond breaker, furnishing and disposing of standby materials for temporary roadway structural section, constructing, maintaining, removing, and disposing of temporary roadway structural section, and quality control program, shall be considered as included in the contract price paid per cubic meter for replace concrete pavement (Rapid Strength Concrete), and no additional compensation will be allowed therefor.

If calibration of volumetric batch-trucks is performed more than 160 km from the project limits, additional inspection expenses will be sustained by the State. Whereas it is and will be impracticable and extremely difficult to ascertain and determine the actual increase in these expenses, it is agreed that payment to the Contractor for Replace Concrete Pavement (Rapid Setting Concrete) will be reduced \$1000.

**BID ITEM LIST**  
**08-47214**

Item No.	Item Code	Item Description	Unit of Measure	Estimated Quantity	Unit Price	Item Total
21	120300	TEMPORARY PAVEMENT MARKER	EA	3540		
22	128650	PORTABLE CHANGEABLE MESSAGE SIGN	EA	30		
23	129000	TEMPORARY RAILING (TYPE K)	M	49 600		
24	129100	TEMPORARY CRASH CUSHION MODULE	EA	510		
25	129150	TEMPORARY TRAFFIC SCREEN	M	49 600		
26	150206	ABANDON CULVERT	M	380		
27	150662	REMOVE METAL BEAM GUARD RAILING	M	1820		
28	150710	REMOVE TRAFFIC STRIPE	M	222 000		
29	150713	REMOVE PAVEMENT MARKING	M2	130		
30	150722	REMOVE PAVEMENT MARKER	EA	23 200		
31	150742	REMOVE ROADSIDE SIGN	EA	2		
32	150760	REMOVE SIGN STRUCTURE	EA	6		
33	150771	REMOVE ASPHALT CONCRETE DIKE	M	12 100		
34	014157	REMOVE GRATED LINE DRAIN	M	6		
35	150820	REMOVE INLET	EA	10		
36	150859	REMOVE ASPHALT CONCRETE OVERSIDE DRAIN	EA	3		
37	151270	SALVAGE METAL BRIDGE RAILING	M	2040		
38	151274	SALVAGE CONCRETE BARRIER (TYPE K)	M	6110		
39	014158	RECONSTRUCT ASPHALT CONCRETE ENTRANCE TAPER	EA	20		
40	152299	RESET MILEPOST MARKER	EA	5		